

654.04

47 required gap between anchor plate and nut without producing slack in
48 restrainer cable.

49

50 **(2) Inspection.** At least one day before restoring concrete, notify
51 Engineer that restrainer cables are in position and ready for
52 inspection.

53

54 **654.04 Measurement.** Restrainers will be paid on a lump sum basis.
55 Measurement for payment will not apply.

56

57 **654.05 Payment.** Engineer will pay for accepted restrainers on a contract lump
58 sum basis. Payment will be full compensation for work prescribed in this section
59 and contract documents.

60

61 Engineer will pay for following pay items when included in proposal schedule:

62

Pay Item	Pay Unit
Longitudinal Cable Restrainer - _____	Lump Sum
Vertical Cable Restrainer - _____	Lump Sum
Vertical Bar Restrainer - _____	Lump Sum
Longitudinal Bar Restrainer - _____	Lump Sum

72

73

74

END OF SECTION 654